



BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of Work: Drilling of Borewells and Providing Pump and Motor laying pipeline in ward No. 08, Amruthahalli Surrounding area.


Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	5.00	Geophysical investigation at site for sinking borewells for supplying drinking water to the habitation either through the Hand Pump MWS or P.W.S.S, by vertical electrical sounding by adopting Venner or Schlumbergers's method, including econnaissance survey of geological formation. Geophysical investigation of existing ground water in the vicinity, its quality, quantity and acceptability of the users, indicating the location of the site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 metre in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instruments and accessories to work site, engaging technical personal and labour required etc. NOTE: 1) Additional rate on item 1&2 is allowed for drilling in over burden and fixing Casing pipes beyond 20 M (for fixing Casing pipes only) a) Above 20 M and upto 30 M - 15%, b) Above 30 M - 30% (Measurement of overburden is restricted to the depth of casing pipe fixed excluding initial depth of 20M and projection above ground level). 2) A sum of Rs. 100/- is to be deducted for Dry Borewell towards yield test	Each BW	5288.00	Rupees Five Thousand Two Hundred Eighty Eight Only
2	250.00	Sinking of Borewell of 165mm dia clear using super fast hydraulic rig of capacity 300 PSIG & above 1100 CMF & above in all strata including over burdern upto 20 m. Fixing of casing pipes, collars and cap with necessary cutting, threading and welding including transportation of rig and supporting vehicle, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (Excluding cost of casing pipes, collars, cap etc., complete) 0-50mtrs	Rmtr	370.00	Rupees Three Hundred Seventy Only
3	250.00	50-100mtrs	Rmtr	464.00	Rupees Four Hundred Sixty Four Only
4	250.00	100-150mtrs	Rmtr	493.00	Rupees Four Hundred Ninety Three Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
5	250.00	150-200mtrs	Rmtr	572.00	Rupees Five Hundred Seventy Two Only
6	250.00	200-250mtrs	Rmtr	671.00	Rupees Six Hundred Seventy One Only
7	250.00	250-300mtrs	Rmtr	740.00	Rupees Seven Hundred Forty Only
8	250.00	300-350mtrs	Rmtr	868.00	Rupees Eight Hundred Sixty Eight Only
9	250.00	350-400mtrs	Rmtr	937.00	Rupees Nine Hundred Thirty Seven Only
10	300.00	Supply of ISI mark 175mm nominal bore, plain and steel casing pipe grade of steel Fe 410 of wall thickness conforming to IS 4270-2001 and latest amendments, electrical resistance welded steel tubes, material and conforming to IS 1387-1993 and manufactured by basic open hearth electric or basic oxygen process in random length of 5-7m both ends. threaded conforming to IS 554-1985 one end fixed with socket conforming to IS 4270-2001 and the other end with screwed pipes all shall be responsibly free from defects. The tubes shall be responsible straight end should be with ISI marking weighing 25.10kg/m. prices include Collar-Medium duty.	Rmtr	1933.00	Rupees One Thousand Nine Hundred Thirty Three Only
11	5.00	Providing and laying at site of work MS casing caps as per IS 1239 (part II) 1982 with all latest amendments if any for any dia. The thickness of plate used for covering one end shall be 3mm (minimum). The dimensions of caps and collars shall be strictly as per IS 1239 (Part-II) 1982 with all amendments including cost of material and labour charges for fixing, if any etc. complete with all lead and lifts and as directed by the Engineer in charge	Each	164.00	Rupees One Hundred Sixty Four Only
12	117000.00	Fabricating supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size c/a with necessary cable entry pipe with gland and box should be finished with 7 tanks treatment with powder coated paint and finally finished with approved colour etc., complete.	Sq Cm	0.43	and Forty Three Paise Only
13	5.00	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI Union conforming to IS 1239-II, 1991 with latest amendments if any	Each	267.00	Rupees Two Hundred Sixty Seven Only
14	15.00	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI hexagonal nipple conforming to IS 1239-II, 1991 with latest amendments if any.	Each	213.00	Rupees Two Hundred Thirteen Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
15	15.00	Supply and delivery at site wrought middle steel (galvanized) 50 mm dia GI elbow confirming to IS 1239-II, 1991 with latest amendments if any for:	Each	267.00	Rupees Two Hundred Sixty Seven Only
16	5.00	Labour charges for Erection, Electrification and commissioning of Pump sets, including aligning and balancing of all items including supply and erection of two pair of supporting clamps, bore well caps, cable clips and water tight gland cable protectors, bolts, nuts, valve and gauges, tools and equipments etc., involved in the job as per specifications, with necessary tests as per specifications, with testing of as per instructions of engineer incharge of work.	Job	6500.00	Rupees Six Thousand Five Hundred Only
17	5.00	Labour charges for erection of outdoor type panel board and meter board units with all necessary materials and labour, tools and equipments including providing cement concrete foundation bed etc., complete as per specification, with testing of as per instructions of engineer incharge of work.	Job	1450.00	Rupees One Thousand Four Hundred Fifty Only
18	0.08	1.1 kV, XLPE or Heat resistant PVC insulated, PVC extruded Inner Sheath Armoured LTUG Cable as per IS-1554 (Part 1) or IS-7098 Part-1, Armouring strip thickness and resistivity as per IS-3975 16 Sqmm, 4 Core, (11 GI Strips - 4 x 0.8 mm)	Km	141842.00	Rupees One Hundred Forty One Thousand Eight Hundred Forty Two Only
19	5.00	Earthing: Supplying and fixing and wiring earth electrode for grounding circuits IC cutouts and other equipments on the meter board in the pit. The pits should be filled up with equal proportion of salt and charcoal 150mm around the pipe to complete depth. The connection from the pipe to the conduits etc. is to established through GI wire of sizes as per clause 7.3.3 of IS 732 using 12mm bolts, nuts, washers and check nuts, the pipe shall have 16 through holes of 12mm dia	Job	3750.00	Rupees Three Thousand Seven Hundred Fifty Only
20	5.00	Providing, Supplying and fixing suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc. with necessary materials and labour tools and equipments as per instructions of engineer incharge of work. 3½x6 Sqm	Each	375.00	Rupees Three Hundred Seventy Five Only
21	5.00	Supply and fixing polished wood board made of not less than 15mm thick plank on both sides of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws 20" x 20" x 2.5"	Each	326.13	Rupees Three Hundred Twenty Six and Thirteen Paise Only
22	5.00	Providing, supplying to work site, Submersible Pump Set of 150mm dia suitable for bore well and confirming to IS 8034-2000; 3Phase, SS Bowl & Impeller with Low volt Motor as per specifications, as per necessary amendments and instructions of engineer incharge of work. 17.50 HP - 120 LPM @ 308 m = 26 STG Outlet Dia - 2.00"	Each	77963.00	Rupees Seventy Seven Thousand Nine Hundred Sixty Three Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
23	290.00	Supply and delivery of galvanized mild steel tubes of 6mtr standard length heavy duty (C Class) as per IS 1239 (Part-I) 1990 with latest amendments with ISI Mark (one end fitted with Heavy Duty collar and other end fitted with protective cover) 50 MM Dia	Each	3050.00	Rupees Three Thousand Fifty Only
24	3750.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to IS 13:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100 V as per IS-694:2010. 3C x 6 mm ²	Mtr	245.00	Rupees Two Hundred Forty Five Only
25	5.00	Supplying fully automatic star-delta starter unit push button type with suitable wires, 3 contactors, one adjustable thermal timer mounted on a common base plate held in steel enclosure for use on 400/440 V 3 phase and wired after fixing to the existing wooden board for motor Above 12.5 HP upto 25 HP	Each	8764.00	Rupees Eight Thousand Seven Hundred Sixty Four Only
26	5.00	Supply and delivery at site of brand new best make gate valve as per IS 778/1984 with ISI Mark and as per its latest amendments Size 50 mm	Each	1688.00	Rupees One Thousand Six Hundred Eighty Eight Only
27	5.00	Supply and delivery at site of brand new best make non-return valve as per IS 778/1984 with ISI Mark and as per its latest amendments Size 50 mm	Each	1250.00	Rupees One Thousand Two Hundred Fifty Only
28	5.00	Supply and delivery at site delivery of best indigenous brand new MCB (Miniature Circuit Breakers) of required capacity as per IS 88228/1978 and its latest amendments and with ISI Mark of 6/10/16/20/25/40 Amps with scalable box.	Per Pole	1150.00	Rupees One Thousand One Hundred Fifty Only
29	15.00	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete....	No.	401.00	Rupees Four Hundred One Only
30	489.60	Earth work excavation for pipeline trenches in all kinds of soils by mechanical means as per drawing and technical specifications, including setting out, construction of shoring, strutting, barricading, caution lights, bracing, using sight rails & bonding rods at every 100 mm wherever necessary as directed, removal of stumps and other deleterious matter, dressing of sides and levelling the bottom of trench to the extent required, utilising the available excavated earth locally for the work etc., and all other appurtenances complete in the following strata. All kinds of soils. Depth upto 1.50 m	Cum	288.20	Rupees Two Hundred Eighty Eight and Twenty Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
31	1360.00	Providing and installing at site of work P.V.C. pipes including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour charges and all lift charges, handling charges including encasing the pipe around to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. complete.75mm(weight of pipe -0.917 kg)	Mtr	220.00	Rupees Two Hundred Twenty Only
32	489.60	Refilling available earth around trenches/pipelines, cables in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50 m , and lift upto 1.5 m. Including cost of all labour complete as per specifications	Cum	176.00	Rupees One Hundred Seventy Six Only


 ಮುಖ್ಯ ಅಭಿವೃದ್ಧಿ ಇಂಜಿನಿಯರ್
 ಕೆ.ಎಂ.ಎಂ.ಎ. ವಲಯ


 Executive Engineer
 Byatarayanapura Division
 BBMP, Bangalore - 92
 BBMP, Bangalore - 92

Note:

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

- 1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- 2 Unit rates and prices shall be quoted by the Tender in Indian rupees.
- 3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- 4 Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

